

Window Refs: Ground Floor – GW15 (1 No.)
 Window Refs: First Floor – FW15, FW17 & FW27 (3 No.)

Finishes:

- Internal Timber – Clear Laquer 25% Gloss
- Ext Aluminium – PPC RAL 7034
- Gloss Level 77% Gloss

Glazing:

- TO SYSTEM 100 FRAMES
- 6.4mm Clear LAMINATED Outer Pane
- 16mm ARGON Filled Cavity
- 6.4mm Clear Super Low E LAMINATED Inner Pane
- TO SYSTEM 200 FRAMES
- 6.4mm Clear LAMINATED Outer Pane
- 12mm ARGON Filled Cavity
- 6.4mm Clear Super Low E LAMINATED Inner Pane

Ironmongery:

- Locking Espagnolette Handles System 200 / Locking Aluminium Handles System 100
- Spilvent 40 Trickle Vents As Shown
- Velfac Lockable Opening Restrictor Stays


ELEVATION VIEWED FROM OUTSIDE

Bill Ref:	NOT AVAILABLE
Arch Ref/Schedule:	Dwg 01:51:109/110
Window type:	K7
Quantity:	2
Estimate Item:	21 Value:
Variations:	Value:
Total:	

Bill Ref:	NOT AVAILABLE
Arch Ref/Schedule:	Dwg 01:51:109/110
Window type:	K1
Quantity:	1
Estimate Item:	22 Value:
Variations:	Value:
Total:	

Elevation	Ground	First	Second	Total
North East Elevation	-	2	-	2
South East Elevation	-	-	-	-
South West Elevation	1	1	-	2
North West Elevation	-	-	-	-
Total	1	3	-	4

Fixings/Sealants:
 Silicone To Be ARBOSIL 1090
 Outer Seal To Be ILLMOD Compressible Foam Tape
General:
 All Structural Openings, Prepared By Main Contractor, To Be Square & Plumb To Sizes Shown On Drawings



For Construction

A	AS PER ARCHITECT'S COMMENTS	19.11.02
Rev/Description	Contract / Site	Date
	RESIDENTIAL DEVELOPMENT, ST MARTIN'S LANE MICKLEGATE, YORK.	

Contractor
 NIXON HOMES
 MOUNT HOUSE,
 90 THE MOUNT,
 YORK, YO24 1AR
 TEL: 01904 541841, FAX: 01904 541412.

Architect
 DAVID CHAPMAN ASSOCIATES
 GARTH MEWS,
 BISHOPSGATE,
 YORK, YO23 2UE
 TEL: 01904 700941, FAX: 01904 700942

Drawing Title
 Elevations ~ Type Oi
 90mm Timber Mainframe
 VELFAC System 100/200

Contract No.	Drawing No.	Rev.
1800548	117	A
Drawn	Scale/Plot	Checked
GKDC	28.10.02	1:20/A3